



## **ATTENTION BUILDERS:**

Herriman City will be requiring Foundation Drains on every lot in accordance with R405 of the 2006 IRC. We will allow alternative methods as follows at the time of Final Inspections:

- 1. A certified compaction test of all backfilled areas must meet 85% compaction or better.**
- 2. A signed letter stating that all backfilled areas have been water settled and compacted in 2' lifts.**

As of April 1, 2005, Herriman City will be requiring that at least one of these methods be met by the time of Final Inspection. If these requirements are not being met, then the foundation drain must be put in. Builders are responsible for any settling that has or will occur according to R405 of the International Residential Code.